BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

Tender No: BBMP/EE/DD/TEN/06/12-13 Date: 11.02.2013 Item No: 36

SCHDULE-B

NAME OF WORK:Improvements of drains at Bagalagunte Main road Left side in ward No-14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **Sri M RAJASHEKAR**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres complete as per specificafions. iii) Dismantling Stone Masonry. B. Rubble Stone masonry in cement mortar. complete as per specificafions.	Cum	88.92	170.00	Rupees One Hundred Seventy Only
2	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of c10ds complete as per specifications. specification.	Cum	592.80	180.00	Rupees One Hundred Eighty Only
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	85.22	3600.00	Rupees Three Thousand Six Hundred Only
4	Providing and constructing granite / trap I basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	168.95	3000.00	Rupees Three Thousand Only
5	Construction of Available SSM Qty vide	Cum	53.35	1800.00	Rupees One Thousand Eight Hundred Only
6	Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	35.20	4000.00	Rupees Four Thousand Only

M. Rajashekar
Signature of the Contractor

Executive Engineer

7	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	494.00	60.00	Rupees Sixty Only
8	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	296.40	1515.00	Rupees One Thousand Five Hundred Fifteen Only
9	Providing and fixing Pre cast solid concrete kerb stones of size 450x200x400mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc. complete as per specificafions.	No	618.00	260.00	Rupees Two Hundred Sixty Only
10	Providing and applying painting two coats (excluding priming coat) on new wood surface and/or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications.	Sqm	148.20	70.00	Rupees Seventy Only
11	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading, complete as per specifications.	Cum	88.92	70.00	Rupees Seventy Only

M. Raja Meera

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,